

PORTACABIN STAFF ACCOMODATION

Lot Size: 75m x 13m

Cabin Requirements:

- 10 nos. 6m x 4.8m Portacabin with shed for the accommodation unit
- To be put on top of concrete blocks
- Should have 1 smoke detector on each building
- Should have 1 x 6kg Fire Extinguisher
- Building should be Full Fire Rated with QCD approval on the insulation

- 1 no 6m x 4.8m Portacabin as kitchen
- To be put on top of concrete blocks
- With 2 nos. double bowl kitchen sink
- Building to be installed with 4 nos exhaust fan
- To be fabricated with food preparation table inside
- Should have 1 x 6k Fire Extinguisher
- Building should be Full Fire Rated with QCD approval on the insulation

- 1 no 6m x 2.4m Portacabin as toilet
- To be put on top of concrete blocks
- With 5 nos. Western Type Toilet cubicles
- Each cubicle to be installed with its own shattaf and toilet paper holder
- With 5 nos wash basins
- With 5 nos mirrors
- With 3 nos exhaust fans
- Building should be Full Fire Rated with QCD approval on the insulation

- 1 no 6m x 2.4m Portacabin as shower unit
- To be put on top of concrete blocks
- With 5 nos. Shower cubicles
- With 5 nos wash basins
- With 5 nos mirrors
- With 3 nos exhaust fans
- Building should be Full Fire Rated with QCD approval on the insulation
- With 20 Gallon Capacity Water Heater